INDIVIDUAL PROPERTY/DISTRICT MARYLAND HISTORICAL TRUST INTERNAL NR-ELIGIBILITY REVIEW FORM

| Property/District Name: Standard Oil Company Filling Station Survey Number: PG68-91 | | | |
|---|--|--|--|
| Tax Parcel#: Block 4; Lots 35, 36, and 37 | | | |
| Project: MD Alt 1 (Bladensburg Rd) Planning Study from D.C. Line to 40 th Ave Agency: MDOT-SHA | | | |
| Site visit by MHT Staff:noyes Name Date | | | |
| Eligibility recommended Eligibility not recommended X | | | |
| Criteria: _A _B _C _D Considerations: _A _B _C _D _E _F _G _None | | | |
| Justification for decision: (Use continuation sheet if necessary and attach map) | | | |
| The Standard Oil Company Filling Station at 3800 Bladensburg Road is not eligible due to the fact that it does not meet National Register Criteria A, B, C, or D. Preliminary research has not revealed any association between the dwelling and events that have made a significant contribution to the broad patterns of our history (Criterion A) or the lives of persons significant in our past (Criterion B). Although the building provides an example of a Craftsman-style bungalow, it is neither unusual nor distinguished; it does not represent the work of a master or display high artistic merit (Criterion C). There is no evidence that the property is likely to yield information important in history or prehistory (Criterion D). Thus, the property is not National Register-teligible. | | | |
| Documentation on the property/district is presented in: Maryland Historical Trust Inventory Form | | | |
| and MD Alt 1 (Bladensburg Rd) from D.C. Line to 40 th Ave Planning Study Summary of Results | | | |
| Prepared by: Traceries, 5420 Western Ave., Chevy Chase, MD 20815 Reviewer, Office of Preservation Services January 1998 Date | | | |
| NR program concurrence: Yesnonot applicable 2 2 4 5 6 5 Reviewer, NR Program Date | | | |

CAPSULE SUMMARY

3800 Bladensburg Road

(PG 68-91)

The Standard Oil Company Filling Station at 3800 Bladensburg Road, formerly the corner of

Washington-Baltimore Boulevard and Barney Street, was built soon after December of 1923. The

filling station, erected by the Standard Oil Company of New Jersey, appears to be the result of

increased automotive traffic on Bladensburg Road during the early 1920s. Between 1919 and 1920,

Cottage City was transformed from a rural to a suburban city. In 1922, funds were allocated by

Congress to pave this busy thoroughfare. By 1923, bus transportation began replacing the failing

trolley line. The increase in residents, number of motor vehicles, and the emphasis on gas supported

transportation made this site well suited for a filling station. The Standard Oil Company of New

Jersey operated the filling station during this time, maintaining ownership of the property for forty-

one years.

Designed in the Craftsman-style of architecture, the filling station is a one-story, one-bay wide brick

building. A one-story, one-bay porte-cochere dominates the main facade. The porte-cochere is

supported by brick piers and parged square posts. The filling station is set on a brick foundation laid

in stretcher bond. A hipped ceramic tile roof with wide overhanging enclosed eaves and a wide

entablature, ornamented with painted American flags, rests above the original building. The interior

brick chimney, which is parged and has a corbeled cap, rises above the northwest hip of the ceramic

tile roof. A large 1940s addition was constructed at the northwest end of the filling station. A shed

roof, with parapet walls on the northeast and southwest sides, sits above the concrete block office.

| MARYLAND HISTORICAL TRUST MD INVENTORY OF HISTORIC PROPERTIES | Inventory No. <u>PG68-91</u> |
|--|--|
| | |
| historic name <u>Standard Oil Company Fill</u> common/other name <u>Queens Motor Company</u> | ing Station |
| 2. Location | |
| street & number 3800 Bladensburg Rd. city or town Cottage City vicinity st county Prince George's code 033 zip o | not for publication ate <u>Maryland</u> code <u>MD</u> code <u>20722</u> |
| 3. State/Federal Agency Certification | N/A |
| 4. National Park Service Certification | N/A |
| 5. Classification | |
| Ownership of Property (Check all that app _X private public-local public-State public-Federal | |
| Category of Property (Check only one box) X building(s) district site structure object | |
| 0 0 s 0 0 s | buildings sites structures objects Total |
| Is this property listed in the National I Yes Name of Listing No _X | |

Inventory No. PG68-91 Page 2

| 6. Function | or Use |
|-------------------|--|
| | ctions (Enter categories from instructions) OMMERCE/TRADE Sub: Specialty Store |
| | tions (Enter categories from instructions) OMMERCE/TRADE Sub: Specialty Store |
| | on ==================================== |
| foundat roof _ | nter categories from instructions) ion <u>Solid: Brick, Stretcher Bond</u> Hipped: Ceramic Tile Masonry: Brick, Stretcher Bond |

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

Inventory No. <u>PG68-91</u> Page 3

| 8. Statement of | ====================================== |
|-----------------|--|
| Applicable Nat: | ional Register Criteria (Mark "x" in one or more criteria qualifying the property for National |
| A | Property is associated with events that have made a significant contribution to the broad patterns of our history. |
| В | Property is associated with the lives of persons significant in our past. |
| _X C | Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction. |
| D | Property has yielded, or is likely to yield information important in prehistory or history. |
| Criteria Consid | derations (Mark "X" in all the boxes that apply.) |
| A | owned by a religious institution or used for religious purposes. |
| В | removed from its original location. |
| C | a birthplace or a grave. |
| D | a cemetery. |
| E | a reconstructed building, object, or structure. |
| F | a commemorative property. |
| G | less than 50 years of age or achieved significance within the past 50 years. |

Inventory No. PG68-91 Page 4

| | ace (Enter categories from instructions) Architecture Commerce | |
|-----------------------------------|--|---|
| - | COMMETCE | |
| Period of Significa | ance <u>ca. 1923-1964</u> | |
| Significant Dates . | ca. 1923 | |
| | | |
| Significant Person | (Complete if Criterion B is marked above) | |
| Cultural Affiliation | on <u>Undefined</u> | |
| Architect/Builder . | Unknown | |
| Narrative Statemen the property.) | t of Significance (Explain the significance of | = |
| S | ee Continuation Sheet No. <u>8-1</u> | |

Inventory No. <u>PG68-91</u> Page 5

9. Major Bibliographical References

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Prince George's County Land Records, Recorder of Deeds, Prince George's County, Upper Marlboro, Maryland.

Nelson's Washington Suburban Directory of Maryland and Virginia Towns Adjacent to the District of Columbia, 1923. Justus C. Nelson, 1923.

Polk's Washington Suburban Directory of Maryland and Virginia Towns Adjacent to the District of Columbia, 1930-1931. R.L. Polk & Company, Publishers, 1930.

A History of the Town of Cottage City, Maryland. Compiled by Raleigh A. Donley, Jr. for the Bicentennial Committee, May 8, 1976.

Maryland Inventory of Historic Properties Standard Oil Company Filling Station 3800 Bladensburg Road Inventory No. <u>PG68-91</u> Prince George's County, MD Page 6 ______ 10. Geographical Data _______ Acreage of Property 12,870 square feet Verbal Boundary Description (Describe the boundaries of the property.) The property at 3800 Bladensburg Road is designated as Lots 35, 36, and 37 of Block 5 of Cottage City, Maryland as indicated on Map 50, Grid A4, Subdivision 2804. Boundary Justification (Explain why the boundaries were selected.) The property at 3800 Bladensburg Road has historically been associated with Lots 35, 36, and 37 of Block 5 of Cottage City, Maryland as indicated on Map 50, Grid A4, Subdivision 2804 since its construction circa 1923. ______ 11. Form Prepared By _____ name/title Kristyna G. Olsen, Architectural Historian organization Traceries date January 20, 1998 street & number 5420 Western Avenue telephone 301/656-5283 city or town Chevy Chase state MD zip code 20815 _____ 12. Property Owner ______ name Fred Bari street & number <u>3800 Bladensburg Road</u> telephone _

city or town <u>Cottage City</u> state <u>MD</u> zip code 20769

Inventory No. PG68-91

Section __7_ Page __1_

Standard Oil. Co. Filling Station name of property
Prince George's County. MD
county and state

Designed in the Craftsman-style of architecture, the circa 1923 filling station located at 3800 Bladensburg Road is a one-story, one-bay wide brick building. A one-story, one-bay porte-cochere dominates the main facade. The porte-cochere is supported by brick piers and parged square posts. The filling station is set on a brick foundation laid in stretcher bond. A hipped ceramic tile roof with wide overhanging enclosed eaves and a wide entablature, ornamented with painted American flags, rests above the original building. The interior brick chimney, which is parged and has a corbeled cap, rises above the northwest hip of the ceramic tile roof. A large 1940s addition was constructed at the northwest end of the filling station. A shed roof, with parapet walls on the northeast and southwest sides, sits above the concrete block office.

Located at the north corner of Bladensburg Road and 38th Avenue, the site at 3800 Bladensburg Road slopes up 38th Avenue to the northwest. A paved car lot surrounds the building. The northeast edge of the property is defined by a wood fence.

EXTERIOR DESCRIPTION:

The main facade, or southeast elevation, is one-story in height and one-bay wide. The elevation is pierced by two large original, one-light fixed windows with brick rowlock sills and square-edged wood surrounds. The transom above the paired windows has been enclosed. A one-story, one-bay porte-cochere stands in front of this elevation. The porte-cochere is supported by white-washed brick piers and parged square posts. The hipped ceramic tile roof and wide entablature are continuous over both the porte-cochere and the original building. The northwest addition is visible from the facade. It projects beyond the rear of the original filling station to the northeast and southwest. A single flush wood door with a wood surround punctures the southeast end of the rear addition.

The northeast elevation clearly illustrates significant alterations made to the one-story filling station. This elevation was originally two bays wide. The northwest addition of the one-story, concrete block office increased the overall length of the filling station by one-third. One window was located in the original portion of this elevation, but this opening has been infilled with concrete block. The solider course brick lintel and rowlock sill

Inventory No. <u>PG68-91</u>

Section __7 Page _2__

Standard Oil Co. Filling Station name of property
Prince George's Co., MD
county and state

are still visible. At present, the only opening in the northeast elevation occurs in the office addition. A single flush metal door pierces the eastern end of the addition.

The northwest elevation of the original filling station is completely obscured by the one-story, 1940s office addition. The office is punctured by two randomly placed window openings. A one-light fixed wood window is extant. The second window opening has been infilled with plywood and mechanical equipment. Both openings have rowlock sills. The northeast and southwest parapet walls of the addition terminate at the upper corners of this elevation.

The one-story southwest elevation addresses 38th Avenue. A large window opening in the original filling station has been infilled with concrete block and a single flush metal door. The solider course brick lintel and rowlock sill of the infilled window are still visible. The northwest addition is pierced by one fixed two-light metal window and one fixed one-light wood window. Both windows have brick rowlock sills. The northwest addition is also punctured by a single flush metal door.

OUTBUILDINGS:

A one-story, two-bay wide office with a side entrance is located to the northwest of the main building. This 1960s wood frame office has stuccoed walls and a shed roof clad in metal sheeting. Two large fixed one-light windows dominate the main elevation.

Inventory No. <u>PG68-91</u>

Section 8 Page 1 Standard Oil Co. Filling Station name of property
Prince George's Co., MD county and state

The Standard Oil Company Filling Station at 3800 Bladensburg Road, formerly the corner of Washington-Baltimore Boulevard and Barney Street, was built soon after December of 1923. The filling station, erected by the Standard Oil Company of New Jersey, appears to be the result of increased automotive traffic on Bladensburg Road during the early 1920s. Between 1919 and 1920, Cottage City was transformed from a rural to a suburban city. In 1922, funds were allocated by Congress to pave this busy thoroughfare. By 1923, bus transportation began replacing the failing trolley line. The increase in residents, number of motor vehicles, and the emphasis on gas supported transportation made this site well suited for a filling station. The Standard Oil Company of New Jersey operated the filling station during this time, maintaining ownership of the property for forty-one years.

Automobiles and the accompanying new structures to service, maintain and house them changed the face of the urban street and rural roadways across the country at the beginning of the twentieth century. Through all its design manifestations, from the earliest simple shed and shelter-type stations, the artistic structures of the 1920s and 1930s, the modernistic forms of the mid-twentieth century and on to today's minimalist structures, the gas station reminds us of the golden days of service to the automobile.²

The Standard Oil Company Filling Station is a symbol of the rise of the automobile in this country. Designed to fit harmoniously into the existing context and to promote a solid and respectable image, the gas stations of this period were intended to be viewed as civic assets and, in fact, did much to dispel the poorly regarded image of previously constructed gas stations.

The property is located within the town of Cottage City, which was gradually developed between 1915 and 1930. The Highlands Company, incorporated in 1888, purchased approximately sixty-four acres of land lying between the B&O Railroad line and the Baltimore-Washington Turnpike; an area then known as "The Highlands." In

¹ A History of the Town of Cottage City, Maryland. Compiled by Raleigh A. Donley, Jr. for the Bicentennial Committee, May 8, 1976, p 28-30.

² Michael Karl Witzel, *The American Gas Station* (Osceola, WI: Motor Books International Publishers, 1992), p.7.

³ Land Records of Prince George's County, Liber 34, Folio 317.

Inventory No. PG68-91

Section 8 Page 2

Standard Oil Co. Filling Station name of property
Prince George's Co., MD
county and state

May 1906, the full sixty-four-acre tract was sold to three men, J. Harris Rogers, James C. Rogers, and Richard N. Ryon, who had the area platted under the name "Cottage City" in 1906. Despite its accessibility to downtown Washington, DC via the Bladensburg Road electric streetcar line, several efforts to develop the area failed. It was not until 1915 that Charles M. Lightbown, who had begun buying up lots in the newly platted town in 1906, borrowed money to construct five modest frame "cottages" which he sold to working-class families. By 1925, the town of Cottage City had developed into a substantial suburb with access to the District of Columbia via Bladensburg Road and the B&O Railroad. Today, the town contains over 322 single- and dual-family dwellings and around thirty apartment units.

The filling station is sited on Lots 35, 36, and 37 of Block five within the limits of Cottage City. The Standard Oil Company purchased Lot 37 from Augustus and Letitia Plumber in November of 1923 and Lots 35 and 36 from Charles and Maud Lightbown in December of that same year. The Standard Oil Company of New Jersey, later to be called the Humble Oil Refining Company of Delaware, retained possession of the filling station until June of 1964, when the property was purchased by Tracy and Angela Haines. The property most likely took on its present function as a automobile sales lot after the 1964 transfer of ownership. Between 1964 and 1984, the property was sold and repurchased by the Haines family. The current owner, Fred Bari, bought the land in March of 1988.

This Craftsman-style filling station is a typical example of filling station architecture from the 1920s. The ceramic tile hipped roof and porte-cochere of 3800 Bladensburg Road were common elements utilized in this type of building. The location of this building along Bladensburg Road is also consistent with its

⁴ Land Records of Prince George's County, Liber 34, Folio 317; and Liber 57, Folio 426. The 1906 plat of Cottage City was recorded in Liber B.D.S. 1, Folio 10.

 $^{^{5}}$ A History of the Town of Cottage City, Maryland, p.31.

⁶ According to Liber 3061, Folio 246, the Humble Oil Refining Company of Delaware was the successor by merger to Esso Standard Oil Company, formally the Standard Oil Company of New Jersey. Prince George's County Land Records, Recorder of Deeds, Prince George's County, Upper Marlboro, Maryland.

Inventory No. PG68-91

Section 8 Page 3 Standard Oil Co. Filling Station name of property
Prince George's Co., MD county and state

function. Bladensburg Road, with its connection to Washington and Baltimore, provided a great influence over the development of domestic and commercial architecture in this area. The location of the Standard Oil Company Filling Station was a natural result of the strong commercial development directly along this well traveled route.

Inventory No. PG68-91

Standard Oil. Co. Filling Station

name of property

Prince George's Co., MD

county and state

HISTORIC CONTEXT:

Geographic Organization:

Western Shore

Chronological/Development Period (s):

Industrial/ Urban Dominance (1870-1930)

Modern Period (1930-present)

Prehistoric/Historic Period Theme (s):

Architecture, Landscape, and Community

Planning Economic

RESOURCE TYPE(S)

Category: Building

Historic Environment: Suburban

Historic Function (s): COMMERCE/TRADE/ Specialty Store

Known Design Source: Unknown

Standard Oil Co. Filling Station name of property Prince George's Co., MD

county and state

Chain of Title:

DEED A: Lot 37

July 1, 1918:

J. Harris Rogers of Hyattsville to Augustus J.

and Letitia M. Plummmer

Lot 21; Block 4 Cottage City and

Lot 37; Block 5 Cottage City

Land Records of Prince George's County

Liber 134 Folio 147

November 30, 1923: Augustus J. and Letitia M. Plumber to Standard

Oil Company of New Jersey

Lot 37 of Block 5 Cottage City

Land Records of Prince George's County

Liber SDH 204 Folio 115

DEED B: Lots 35, 36

January 3, 1910:

J. Harris Rogers, James C. Rogers and Richard

N. Ryon to Edwin W. Spalding

a portion of land of originally containing 64 acres, part of which was subdivided by the grantors and called "Cottage City" (Plat recorded in Liber B.D.S. 1 Folio

Land Records of Prince George's County

Liber 57 Folio 426

September 24, 1923: Edwin W. and Katherine L. Spalding to Charles

M. and Maud E. Lightbown

Lots 32, 33, 34, 35, 36; Block 5 Cottage City

Land Records of Prince George's County

Liber 195 Folio 94

December 19, 1923: Charles M. and Maud E. Lightbown to Standard

Oil Company

Lots 35, 36; Block 5 Cottage City

Land Records of Prince George's County

Liber SDH 204 Folio 121

Standard Oil. Co. Filling Station name of property Prince George's Co., MD county and state

June 22, 1964:

Humble Oil Refining Company of Delaware (Successor by merger to Esso Standard Oil Company formerly Standard Oil Company of New Jersey) to Tracy L. Haines and Angela C.

Haines

Lots 35, 36, 37; Block 5 Cottage City Land Records of Prince George's County

Liber 3061 Folio 246

February 25, 1969: Tracy L. Haines to Free State Properties, Inc.

Lots 35, 36, 37; Block 5 Cottage City Land Records of Prince George's County

Liber 3691 Folio 304

October 28, 1974:

Free State Properties, Inc. to Poe W. and

Angela C. Haines

Lots 35, 36, 37; Block 5 Cottage City Land Records of Prince George's County

Liber 4428 Folio 811

September 28, 1984: Poe W. and Angela C. Haines to Thomas B. and

Mary June Ricker, Jr.

Lots 35, 36, 37; Block 5 Cottage City Land Records of Prince George's County

Liber 5981 Folio 117

March 17, 1988:

Thomas B. and Mary June Ricker, Jr. to Fred

Bari

Lots 35, 36, 37; Block 5 Cottage City Land Records of Prince George's County


Liber 6922 Folio 919

SKETCH MAP

Standard Oil Company Filing Station

3800 Bladenslava Rd PG 68-91

Cottage City, MD, Prince George's County



779-1502 AUTOSALE

3800 Bladensburg Rd - Standard Oil Company Filing Station Prince George's 6 MD Tracenes 1/98

Maryland SHPO

1 of 5

Filling Station, SE Elevation



PG: 68-91
3800 Bladensburg Rd - Standard Oil Company Filing Station
Prince George's Co., MD
Tracenes
198
Maryland SHPO
Filling Station, NE Elevation

20P5



PG: 108-91
3800 Bladenslavy Rd. - Standard OII Company Filing Station
Prince George's Co., MD
Tracenes
198
Maryland SHPO
Filling Station, NW Elevation



3800 Badensburg Ed. - Standard Oil Company Filing Station Prince George's Co., MD Traceries Maryland SHPO Filling Station, SW Elevation



PG: 68-91
3800 Bladensburg Rd. - Standard Oil Filing Station
Prince George's Co., MD

Traceries
1/98
Maryland SHPO

Office, Sw Elevation

5095